Lockdown Guidance for Beer Dispense Systems

If your able to clean, then great please do and then flush into water, you can leave the lines in water for approximately 2 weeks. (if your unable to do this please attempt to leave lines dry rather than left for an extended period in beer or water). After this period, you can then blow the lines dry and leave them empty for a further 2 weeks and then REPEAT the cycle. Blowing the lines dry can be achieved by connecting couplers to the cleaning line with the plungers on fob jars placed in the cleaning position. Turn on cleaning gas pump (i.e. gas line feeding that coupler) and push water through by opening taps in the bar until all the water comes out and gas only remains.

Repeat above every 2 weeks i.e. water / dry / water / dry and so on and so on

Please Treat your cask lines in the same way as above

NB Leave remote (python) coolers and under bar coolers switched off, and turn off gas at bottles, If you still have unopened kegs in the cellar, we advise leaving the cellar cooling switched on to preserve the life of the stock, couplers should be sprayed with sanitizer and left on cleaning ring ,cleaning sockets also cleaned , cask lines off the floor, taps and filters cleaned and placed safely, empty casks and kegs removed from cellar , cellar floor and walls washed down In the Bar Remove nozzles, clean thoroughly under warm running water or sanitizing solution and leave to air dry or re fit to fonts . Ensure glasswasher is cleaned and drained -spray all internal surfaces with food-grade sanitizer Remove filter and spray arms, and clean • Leave door open to allow air circulation

Nb if your unable to do above please attempt to leave lines dry rather than left for an extended period in beer or water

❋ For additional help please call your local Clear Brew franchised owner/ technician who will be able to give verbal advice.